


landscapeforms®

redline™





Redline is a resolutely contemporary bench that expresses the movement and dynamism of the urban environments for which it was designed.

Landscape architect Tom Balsley cites the way materials are used in airplanes as inspiration for his striking new product for Landscape Forms. With Redline, he set out “to deconstruct the bench and approach it with a different structural attitude.” The result is a bench with minimal framing in which shape provides structure.

Redline achieves its form and visual distinction with a continuous sheet of perforated steel folded to create seat, back and a generous overhang at the top back that makes the bench handsome from all angles. The frame is simple cut steel. The design language complements the steel and glass of contemporary architecture and meets the demand for sophisticated, strong and easy to maintain furniture in urban spaces. Redline is a natural for transportation, public buildings, and corporate and public plazas.

## Our Purpose Is To Enrich Outdoor Spaces

We believe in the power of design and its ability to influence and elevate the quality of public space. High quality products and outstanding customer experience makes us one of the world's premier designers and manufacturers of outdoor commercial furnishings.

## Redline™ Specifications

### Benches





Sturdy carbon steel frame supports backed or backless benches. Bench is available in 48" or 70" length. Bench comes standard with no arms, and perforated back and seat for heat release. Optional end and center arms available on both backed and backless benches.

Support end frames are of 3/4" steel. Seating surface is made of a laser cut steel panel, to which the end frames are bolted. Redline may be specified in freestanding, embedded or surface mount. Surface mount bench includes custom surface mount tabs. Embedded support style is fitted with four stainless steel threaded rods that slip into adhesive-filled holes drilled into the concrete base. Freestanding bench ships with glides. Redline ships fully assembled.

Redline meets BIFMA performance and safety standards.

backless

backed



48"

70"

48"

70"

21" x 17" x 48"

21" x 17" x 70"

25" x 33" x 48"

25" x 33" x 70"


d x h x l

### Arm Options


Arms are available for either backed or backless benches. All arms are steel and welded to the seat or back surface. Arms may be specified for both ends, as well as the center position (48" length) and intermediate positions (70" length).




### Mounting



freestanding



embedded



surface mount

### Finishes

Metal is finished with Landscape Forms' proprietary Pangard II polyester powdercoat, a hard yet flexible finish that resists rusting, chipping, peeling and fading. Call for standard color chart.

### To Specify

Specify bench model, length, backless or backed and with or without arms and arm placement. Specify powdercoat color, and freestanding, embedded or surface mount.

### [www.landscapeforms.com](http://www.landscapeforms.com)

Download product photos, brochures, color charts, SketchUp components, technical information, CAD details, CSI specifications, assembly instructions.

Redline design is patent pending.

Redline is designed by Thomas Balsley.

Specifications are subject to change without notice.

Location photography: Charlotte Light Rail System, Charlotte, NC.

Landscape Forms supports the LAF at the Second Century level.

© 2008 Landscape Forms, Inc. Printed in U.S.A.



Metal is the world's most recycled material and is fully recyclable. Consult our website for recycled content for this product. Powdercoat finish on metal parts contains no heavy metals, is HAPS-free and has extremely low VOCs.



Mixed Sources  
Product group from well-managed forests and other controlled sources  
Cert no. SW-COC-1530



Certified Renewable Energy  
green-e.org

Landscape Forms is proud to specify FSC and Green-e certified paper. This paper meets the Forest Stewardship Council's standards for responsible forest management and is made using certified renewable energy.

landscapeforms®

800.521.2546 269.381.3455 fax

431 Lawndale Avenue, Kalamazoo, MI 49048

[www.landscapeforms.com](http://www.landscapeforms.com)